



Office of
Deputy Commissioner
of Maritime Affairs

THE REPUBLIC OF LIBERIA
BUREAU OF MARITIME AFFAIRS

8619 WESTWOOD CENTER DRIVE
SUITE 300, VIENNA, VA. 22182 USA
Telephone (703)-790-3434
Telefax: (703)-790-5655
E-Mail: technical@liscr.com

Technical Letter 2007-01
March 1, 2007

Subject: Inspection and Maintenance of Shipboard Elevators

This technical letter is issued in order to detail the this Administration policy with regards to ship survey of shipboard elevators

1. Acceptance Tests

New elevators, after completion and before being placed in service, are to be subjected to acceptance tests and inspections on the vessel to determine that the installation conforms to the requirements of the elevator manufacturer, the vessel's class society ,as applicable, and that all safety equipment and functions are properly installed and functioning. A similar test and inspection is to be made following a major alteration to an existing elevator installation. Acceptance tests are to be witnessed by n attending class society surveyor. The following are to be included in the test program.

- Test of car safety with rated load in car
- Test of counterweight safety
- Test of governor tripping speed
- Test of hoistway and car door interlocks and escape hatch interlocks
- Operating test of entire installation including check of car and position indicators
- Operating test of manual hoisting device
- Test of driving machine brake with maximum load weight plus 25% of rated load
- Test of buffers
- Test of slack rope switch

2. Maintenance, Periodic Tests and Inspections

- a. Routine and periodic maintenance of the elevator shall be carried out in accordance with the manufacturer's instructions and at intervals specified by the elevator manufacturer.
- b. Periodic tests and inspections of the elevator installation are to be made during the vessel's annual and intermediate and renewal surveys or at more frequent intervals if so specified by the elevator manufacturer. . The following tests are to be conducted and witnessed by the Surveyor.

- Test of car and counterweight safeties
- Test of governor tripping speed
- Test of driving machine brake
- Test of hoistway and car door interlocks and escape hatch interlocks

Inspection is to be made of the entire installation at this time with particular attention to the following.

- Hoisting cables
- Driving machine brake
- Safeties
- Guide rails and guide shoes or rollers


3. Capacity Plate and Data Plate

A capacity plate of engraved metal is to be permanently installed in each elevator car and is to indicate the safe capacity of the car in N (kgf, lbf) and number of persons. A data plate of engraved metal is to be permanently mounted on each car frame and is to indicate the following.

- Weight of complete car including safety and all auxiliary equipment attached to car
- Rated load and speed
- Wire rope data as per 4.11.5
- Manufacturer's name and date of installation

If there are any questions relating to this Technical Note, please contact Chief of the Technical Department at technical@liscr.com

Regards,



Anthony Dupree, for
Vice President, Technical and Communications - LISCRC
for the Deputy Commissioner of Maritime Affairs
Republic of Liberia